

**ANNEXURE - I (B)**  
**TECHNICAL DETAILS FOR ROADS**

DIVISION : (H) RURAL ROADS, TRICHY

DISTRICT : PERAMBALUR

Sl. No.	Name of work	District	Classification of Work	EXISTING				PROPOSED				INCREASE			No. of CD works (Nos.)
				Road way width (m)	Carriage way width (m)	Pavement thickness (mm)	Status	Road way width (m)	Carriageway width (m)	Pavement thickness (mm)	Status	Road way width (m)	Carriage way width (m)	Pavement thickness (mm)	
1	2	3	4	5	6	7	8	9	10	11	12	13	14	15	16
1	Impts. to Valikandapuram - Neikkuppi road (via) Siruvayalur Km 5/6 - 6/8	Perambalur	Panchayat Road	5.00	-	-	Earthern surface	7.50	-	500	PC with seal coat	2.50	3.75	500	4
2	Construction of bridge at Km 5/10 of Valikandapuram - Neikkuppi road (via) Siruvayalur .	Perambalur	Panchayat Road	-	-	-	-	-	-	-	-	-	-	-	-
3	Impts. to the road from Km 64/10 of T.C. road to Orathur Km 0/0 - 3/0 (via) Vilangudi.	Perambalur	Panchayat Union Road	4.00	2.00	100.00	Wron out WBM surface	7.50	3.75	300	(BT) PC with seal coat	3.50	1.75	200	5
4	Construction of bridge at Km 1/6 of Ayanathur - Kilimangalam Road	Perambalur	Panchayat Union Road	-	-	-	-	-	-	-	-	-	-	-	-

DIVISIONAL ENGINEER (H),  
RURAL ROADS, PUDUKKOTTAI,  
A/C, RURAL ROADS DIVISION,  
TRICHY - 20.